

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2 N R 3 E I-10
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
WHITE OAK 18" N84-1/2E 10 LINKS
WHITE OAK 9" N73W 33 LINKS

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD AT CENTER LINE N/S ASPHALT PAVEMENT AT CENTER LINE ABANDONED COUNTY ROAD (GRAVEL) TO EAST. OCCUPATION LINE TO WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10, T2N, R3E, IOSCO, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" in road box and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 055 DEGREES 38.59' CORNER ANGLE IRON FENCE POST. 1' ABOVE GRADE.
- 127 DEGREES 44.40' SET NAIL/TAG SW/S 30" OAK.
- 236 DEGREES 39.11' SET NAIL/TAG NW/S 26" MULBERRY.
- 324 DEGREES 50.45' SET NAIL/TAG NE/S 26" MULTI-STEM OAK.

FILED

1999 NOV 22 A 10:07

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC #1066m
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

IOSCO TWP.

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 2-3-99, CO. REP JED

Signed by Darrell Hughes

Date NOVEMBER 3, 1999

Surveyor's Michigan License No. 19834