

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2</u> N R <u>3</u> E	J-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1998 OCT 14 P 2:12

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC 917M

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on OCTOBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

IOSCO TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
White Oak 30" South 86 degrees West 58 links
White Oak 16" North 20½ degrees East 49 links

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron pipe 30' East of a North-South fence. ±6' West of two track, 0.25' above grade, ±0.5 miles South of Coon Lake Road.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9, T2N, R3E, IOSCO, set corner with 1¼" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 003 deg. Set Nail / Tag W/S 10" Ash 28.13'
- 080 deg. Set Nail / Tag N/S 12" Basswood 21.95'
- 245 deg. Set Nail / Tag S/S 16" Oak 20.69'
- 281 deg. Set Nail / Tag N/S 24" Oak 6.29'

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3-18-98 CO. REP JED

Signed by Darrell D. Hughes
Surveyor's Michigan License No. 19834



Date OCTOBER 6, 1998