

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2</u> N R <u>3</u> E	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1998 OCT 14 P 2:11

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

9- LSC 915M  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DARRELL D. HUGHES, in a field survey on OCTOBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

IOSCO TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor  
Tamarack 12" South 19 degrees East 10 links  
Tamarack 10" South 58 1/2 degrees West 10 links

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe in downed old East-West fence, 2' East of East edge of 20' wide ditch and 12' South of South edge of said ditch. Ditch runs South, West of corner and runs East, North of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8, T2N, R3E, IOSCO, set corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk.  
Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 018 deg. Set Nail / Tag E/S 14" Box Elder 123.77'
- 108 deg. Fd. Nail / Tag N/S 8" Maple 44.17'
- 157 deg. Set Nail / Tag NE/S 20" Basswood 39.53'
- 182 deg. Set Nail / Tag W/S 12" Basswood 35.55'
- 320 deg. Set Nail / Tag NE/S 14" Maple 101.53'

P.A. 245 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 5-20-98, CO. REP JED

Signed by [Signature]

Date OCTOBER 6, 1998

Surveyor's Michigan License No. 19834

