

SURVEY & REMONUMENTATION

FEB 25 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

SECTION

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2 N R 3 E K-10
2. Property Controlling in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

1998 OCT 14 P 2:11

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC 914M
Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, DARRELL D. HUGHES, in a field survey on OCTOBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (10, K) contains a small circle.

IOSCO TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
Black Ash 8" South 70 1/2 degrees East 23 links
Tamarack 5" North 25 degrees West 27 links

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" iron pipe 2' South of North edge of a East-West ditch. Found in flow line of said ditch. The said pipe stands +/- 4' above water line of ditch.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10, T2N, R3E, IOSCO, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" inside top of existing 4" pipe and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 084 deg. Set Nail / Tag S/S Elm cluster 68.48'
067 deg. Set Nail / Tag S/S 6" Cherry 16.20'
290 deg. Set Nail / Tag NE/S 12" Elm 42.40'
350 deg. Set Nail / Tag W/S 10" Elm Stump 50.82'

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3-18-98, CO. REP JED

Signed by [Signature]
Surveyor's Michigan License No. 19834

Date OCTOBER 6, 1998