

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 12 22 PM '93
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

FILED

For corners in

Livingston
 (County)

Located In: Corner Code ##

1. Public Land Survey	T <u>2N</u> R <u>3E</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

L.S.C. #129m
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Darrell D. Hughes, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825
 Tamarack 16" N57W 9 lks.
 Tamarack 14" N80½E 47 lks.

SUSAN A.
 REMOND
 1993
 COMMISSION

*Additional historical information on back of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13, T2N, R3E, IOSCO, replaced 1/2" iron rod with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, 30" below grade, 20' E of E end E/W ditch, 15' S. of extended E/W ditch and is accepted as a careful and faithful reestablishment of the position of the original corner.
 277 DEG. 41.19' SET 1 1/4" X 36" IRON PIPE/ BRASS DISK FOR NW COR SEC 1 (K-1) T1N, R3E, UNADILLA.
 325 DEG. 27.71' SET 1" X 36" IRON PIPE/BRASS WIT DISK.
 305 DEG. 46.03' SET 1" X 36" IRON PIPE/BRASS WIT DISK.
 295 DEG. 63.26' SET 1" x 36" IRON PIPE/BRASS WIT DISK.
 WIT. PIPES ARE 9' N OF CL E/W DITCH.

Signed by Darrell D. Hughes Date December 27, 1993
 Surveyor's Michigan License No. 19834

Approved by Liv. Co. Peer Group: December 11, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

IOSCO TOWNSHIP, T2N, R3E

K-13, SOUTHWEST CORNER SECTION 36

FIELD 10-27-1993 D.D.HUGHES AND ASSOCIATES, FOWLERVILLE

Found 1/2" iron rod in farm field, 41.19' East of found 1/2" iron rod for Northwest corner Sec. 1, Unadilla Twp.

1825, corner first set by Sylvester Sibley, Deputy U.S. Surveyor in "Tamarack swamp".

1861, E.N. Fairchilds, County Surveyor, divided Section 36.

1876, Miles Bullock, surveyed Northeast 1/4 Sec. 2, Unadilla, shows falling in wrong direction.

1915, Grant Dunning, County Surveyor, retraced parts of section division.

1965; Lyle Munsell, shows corner 41.19' East of Northeast cor. Sec. 2, Unadilla. GLO= 41.58'

1976, Boss ran extensive traverse for all of Section 36 and into the East 1/2 of Section 35. All corners and 1/4 corners were either found or calculated and given coordinates. 41.19' R&M

1982, Boss set 1/2" iron 41.19' East of 4" iron post. L.1041, P.258.

1990, Hughes fd. 1/2" iron rod and witnessed, job no. 90689