

SURVEY & REMONUMENTATION

FEB 25 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in **SECTION**

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 2 N R 3 E</u>	<u>L-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

1998 OCT 14 P 2:11
NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843
LSC 913M
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on OCTOBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
White Oak 7" South 42 degrees East 5 links
White Oak 6" North 5 degrees West 14 links

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod on fence intersection to North and West. 10' North of extended fence line to East, 16' West of fence to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9, T2N, R3E, IOSCO, set corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 105 deg. Set Nail / Tag S/S 48" Oak 13.07'
- 179 deg. Set Nail / Tag W/S 15" Twin Oak 46.20'
- 265 deg. Set Nail / Tag N/S 12" Oak 17.50'
- 353 deg. Set Nail / Tag E/S 16" Oak 24.60'

PA. 943 1998, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3/18/98, CO. REP JED

Signed by *Darrell Hughes*
Surveyor's Michigan License No. 19834

Date OCTOBER 6, 1998