

SURVEY & REMONUMENTATION

FEB 24 1998

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 NOV 13 P 1:43

NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843

L.S.C. #780m

Register of Deeds Stamp & File Number

For corners in **SECTION**

LIVINGSTON
 (County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|---------------|-----------------------------|-------------|
| 1. Public Land Survey | | <u>T 2 N R 3 E</u> | <u>M-2</u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on OCTOBER 29, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

IOSCO TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
 Ash 14" South 75 degrees West 3 1/2 links
 Ash 20" South 15 degrees East 25 links

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod 7± South of a downed fence running East and West. 300± South of the end of Truhn Road at the centerline of Truhn road extended.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2, T2N, R3E, IOSCO, replaced existing corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 088 deg. Set Nail / Tag S/S 14" Elm 10.23'
- 170 deg. Set Nail / Tag E/S 15" Walnut 28.18'
- 252 deg. Set Nail / Tag SE/S 8" Butternut 9.30'
- 346 deg. Set Nail / Tag E/S 36" Twin-Cherry 71.67'
- 280 deg. Found iron rod with cap #12024 33.00'
- 182 deg. Found 1/2" iron pipe for A-2 T2N,R4E Marion Twp. 238.25'

PA. 345 1980, APPROVED BY LIVINGSTON COUNTY
 PEER GROUP ON 9-17-97 CO. REP JED

Signed by Darrell Hughes

Date OCTOBER 29, 1997

Surveyor's Michigan License No. 19834

IOSCO TOWNSHIP, T2N, R3E

M-2, EAST 1/4 CORNER SECTION 1

FIELD: 9-13-1997

Found 1/2" rerod at ground grade, 7' South of old downed E/W fence, found 1/2" iron rod 33.00' west with cap No. 12024 (A.F. Miller [CHMP]), found 1/2" iron pipe, 238.02' South, for A-1, Marion. Corner falls 300' +/- South of the end of Truhn Road (physical gravel) in low wooded area. Poor for GPS. Prior witness trees were identified, but no nails or tags were found. Set nails on Maple and Cherry, tangent with iron. Measures agree with former ties. I recommend, to the peer group, the acceptance of this point for the location of M-2, based on the following:

- 1825 Sylvester Sibley, U.S. Deputy Surveyor, first set corner.... "North on the East boundary of Section 1, 40.00 chains, set 1/4 section post". P.7-7B
- 1875 +/- Miles Bullock, county surveyor shows distance from M-1 to M-2 to be either 3341.58' or 3407.58'. P.8
- 1971 Henderson-Bates survey for the Detroit Edison Majestic-Cohochtah Corridor, shows 237.77' from rod at M-2, South, to iron at A-2. P.9
- 1977 Patrick Benton shows relationship between A-1 and A-2, Marion, by distance, direction and witness'. P.10-10A
- 1978 A.F. Miller (CHMP) uses M-2 in survey, describes corner and shows witness'. P.11
- 1979 Pat Benton shows relationship between M-1 and M-2. Does not describe corner or give witness.. Comparing his 1977 survey above, gives 239.30' between M-2 and A-2. P.12
- 1979 A.F. Miller (CHMP) shows relationship between M-2 and A-2, with witness' only to M-2. P.13-13A
- 1979 A.F. Miller files Act 74 for M-2. P.14
- 1986 Charles Garlock shows corner in survey, does not describe or witness, shows distance North to M-1 as 3410.21'. P.15
- 1991 Boss shows relationship between M-1 and M-2 with witness' and references M-1/M-2 distances by Garlock and Benton. (0.30' spread between all three surveyors). P.16-16A
- 1992 Boss surveys in Section 6, Marion, shows relationship between A-1, A-2 and M-2. Falling distance on drawing is 238.47', on witness' 238.25'. P.17-17A
- 1997 Hughes witness comparison list. P.18-18A