

**SURVEY & REMONUMENTATION**

**FEB 24 1998**

**FILED**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

1997 NOV 13 P 1:43

NANCY HAVILAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI.  
 48843

For corners in

LIVINGSTON  
 (County)

Located In:

Corner Code #

- |                                    |               |                             |             |
|------------------------------------|---------------|-----------------------------|-------------|
| 1. Public Land Survey              |               | <u>T 2 N R 3 E</u>          | <u>M-4</u>  |
|                                    |               | T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    |               | T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    |               | T <u>    </u> R <u>    </u> | <u>    </u> |
| 2. Property Controlling in Section | S <u>    </u> | T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> | T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> | T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> | T <u>    </u> R <u>    </u> | <u>    </u> |

L.S.C. #782m

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, DARRELL D. HUGHES, in a field survey on OCTOBER 29, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

IOSCO TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor  
 White Oak 32" South 70 degrees West 231 links  
 Aspen 20" South 48 degrees East 118 links

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod 228± North of the intersection of Dutcher Road to South and Lange Road East and West and 0.7± East of a fence running North and South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4, T2N, R3E, IOSCO, replaced existing corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 036 deg. Set Nail / Tag SE/S 18" Tree 37.11'
- 170 deg. Set Nail / Tag W/S 36" Walnut 46.23'
- 185 deg. Set Nail / Tag E/S 18" Oak 36.18'
- 224 deg. Set Nail / Tag NW/S 14" Cherry 6.52'
- 184 deg. Found 1/2" iron rod for A-4 T2N,R4E Marion Twp.

**P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY**  
 PEER GROUP ON 9-17-97 CO. REP JED

signed by *Darrell Hughes*  
 Surveyor's Michigan License No. 19834

Date 10-29-97  
 OCTOBER 29, 1997

IOSCO TOWNSHIP, T2N, R3E

M-4, EAST 1/4 CORNER SECTION 12

FIELD: 9-13-1997

Found 1/2" rerod, 0.3' above ground grade, 0.7' East of North-South farm fence, 228' North of the intersection of Dutcher Road, to South, and Lange Road, East and West. Former witness' agree. Measures 227.98' South to to 1/2" iron rod at A-4, Marion Township. This point was set by Henderson-Bates in 1971 during their survey of Detroit Edison's Majestic-Cohochtah Corridor. As a note, several surveyors in the past have used A-4, Marion as M-4, and some of the following witness labled M-4 are to the point at A-4. Iron falls in wooded area, poor for GPS. I recommend, to the peer group, the acceptance of this point for the location of M-4, based on the following:

- 1825 Sylvester Sibley, U.S. Deputy Surveyor, first set corner...."North on the East boundary of Section 12, 40.00 chains, set 1/4 post." P.7-7A
- 1969 Charles Garlock, shows corner 235.95' North of a spike in Lange Road, does not identify corner or provide witness'. P.8
- 1971 Norm Fahrner, for A-4, "sets 1" X 30" iron pipe 1/2 the distance between (A-3 and A-5)" (and on line ?), files Act 74. P.9
- 1971 Henderson-Bates finds BT (boat) spike for A-7 and sets 1/2" iron rod 228.16' North of spike, on A-4/A-3 line. P.10-10A
- 1972 Marcus Zuhlke, Jr., uses A-4 for M-4. P.11
- 1974 Charles Garlock files Act 74 for A-4, finds 1/2" iron rod and finds two other irons nearby. (The boat spike he set in 1969 and the 1" pipe that Fahrner set in 1971 ?). P.12
- 1975 Pat Benton uses 1/2" iron rods at both A-4 and M-4, shows distance between and shows witness'. P.13-13A
- 1976 Same as above. P.15 and P.17
- 1976 Henderson-Bates shows "Found boat spike" for A-4. P.16
- 1979 A.F.Miller (CHMP) uses 1/2" iron for M-4, shows witness' that match Benton and Bates. P.14
- 1984 Benton uses same corners again. P.18-18A
- 1988 Boss shows relationship between A-4 and A-3. P.19-19A
- 1989 Hughes uses 1/2" irons for M-4 and A-4 in survey, shows relationship and witness'. Field notes of three points for A-4. P.20-20B
- 1990 Matt Brady uses A-4 for M-4. P.21-21A
- 1990 Boss shows relationship between A-4 and A-3. P.22-22A
- 1997 Hughes witness comparison list. P.23-23B