

FEB 24 1998

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1997 NOV 13 P 1:43

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C.#783m

Register of Deeds Stamp & File Number

For corners in		
<u>LIVINGSTON</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>2</u> N R <u>3</u> E	<u>M-5</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

IOSCO TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor  
White Oak 24" South 5 degrees West 78 links  
Black Oak 9" South 80 degrees West 74 links

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod 7± West of centerline of Dutcher Road and 133± North of centerline of Deacon Hill drive to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5, T2N, R3E, IOSCO, replaced existing corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 048 deg. Set Nail / Tag NW/S 60" Oak 40.06'
- 238 deg. Set Nail / Tag SE/S 32" Cherry 33.25'
- 301 deg. Set Nail / Tag NE/S 60" Oak 34.64'
- 276 deg. Found iron rod 33.06"
- 185 deg. Found 1" iron pipe for A-5 T2N,R4E Marion Twp. 209.87'

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 9-17-97 CO. REP JED

signed by Darrell Hughes  
Surveyor's Michigan License No. 19834

Date NOVEMBER 3, 1997

IOSCO TOWNSHIP, T2N, R3E

M-5, NORTHEAST CORNER SECTION 13 AND SOUTHEAST CORNER SECTION 12

FIELD: 9-13-1997

Found 1/2" rerod, 0.6' below gravel road grade, 7' West of centerline of Dutcher Road, 133'+/- North of Deacon Hill Drive to West. Measure 209.87' South to 1" iron pipe at A-5. Agree with older witness' and found 1/2" iron rod 33.06' to West. I recommend, to the peer group, the acceptance of this point for the location of M-5, based on the following:

- 1825 Sylvester Sibley, U.S. Deputy Surveyor, first sets corner... "North on the East boundary of Section 13, 80.00 chains, set post" and (for A-5)... "West between Sections 7 and 18, intersected West boundary 3.27 chains (215.82') South of post (M-5). P.7-7C
- 1966 Lyle Munsell shows corner in survey. P.8
- 1971 Garlock shows corner in survey, sets iron 33' West. P.9
- 1971 Norm Fahrner finds 3/8" iron rod and iron 33.2' West, files Act 74 for M-5 and A-5. P.10-10A
- 1972 Marcus Zuhlke Jr. finds iron, shows witness'. P.11
- 1972 Garlock field notes shows corner. P.12
- 1974 Pat Benton finds 1/2" iron, shows witness'. P.13-13A
- 1975 Boss survey shows corner with witness'. P.14
- 1975 Benton survey shows corner with witness' P.15-15A
- 1976 Boss survey shows corner. P.16
- 1976 Henderson-Bates survey for Detroit Edison, finds rod and shows 209.81' South to A-6. P.17
- 1976 Benton shows corner in survey with distance to M-6. P.18
- 1978 Benton finds 1-1/2" iron pipe at A-5. P.19
- 1980 Benton survey shows corner and distance to A-4. P.20
- 1981 Benton shows corner in survey. P.21
- 1984 Benton shows corner and distance to A-4. P.22-22A
- 1989 Garlock shows relationship between M-5 and A-5 with witness'. P.23-23A
- 1990 A.F. Miller (CHMP) shows corner with witness'. P.24
- 1990 Matt Brady shows corner with witness'. P.25-25A
- 1993 Hughes shows relationship of M-5 and A-5 with witness'. P.26-26A
- 1995 Boss shows corner with witness' and distance to A-5. P.27-27A
- 1996 Boss shows relationship of M-5 and A-5 with witness'. P.28-28A
- 1997 Hughes witness comparisons. P.29-29B