

FEB 24 1998

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

1997 NOV 13 P 1:43

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2 N R 3 E M-6
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

L.S.C.#784m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

IOSCO TWP.

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
White Oak 17" South 56 degrees West 165 links
White Oak 26" North 86 degrees West 212 links

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron rod at centerline of Dutcher Road and centerline of Munsell Road to the West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6, T2N, R3E, IOSCO, replaced existing corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 096 deg. Set Nail / Tag S/S 20" Ash 28.31'
- 266 deg. Set Nail / Tag N/S 18" Cherry 131.93'
- 020 deg. Set Nail / Tag W/S 24" Walnut 61.59'
- 198 deg. Set Nail / Tag W/S 16" Elm 130.08'
- 186 deg. Found 1/2" iron pipe for A-6 T2N,R4E Marion Twp. 210.57'

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 9-17-97 CO. REP JEO

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date NOVEMBER 3, 1997

IOSCO TOWNSHIP, T2N, R3E

M-6, EAST 1/4 CORNER SECTION 13

FIELD: 9-13-1997 D.D. HUGHES AND ASSOCIATES

Found 5/8" rerod at center intersection of Dutcher and Munsell Roads, 0.5' below gravel road grade. Witness' agree back to 1971, when it was set for Detroit Edison's Majestic-Cohoctah Corridor. Good for GPS. I recommend, to the peer group, the acceptance of this point for the location of M-6, based on the following:

- 1825 Sylvester Sibley, U.S. Deputy Surveyor, first sets corner... "North on the East boundary of Section 13, 40.00 chains, set 1/4 section post". P.7-7A
- 1971 Washtenaw Engineering, in March, sets iron for A-6. P.13
- 1971 Norm Fahrner, Wash. Eng. finds 1/2" iron rod for M-6, files Act 74. P.8
- 1972 Charles Garlock shows corner in survey and shows witness'. P.9-9A
- 1973 Garlock shows corner in survey and shows witness'. P.10-10A
- 1973 Gary Stonerock files Act 74 for A-6. P.29
- 1975 Boss survey shows corner with witness'. P.11
- 1975 Benton survey shows corner with witness'. P.12-12A
- 1976 Benton survey shows distance from M-6 to M-5. P.14
- 1978 Benton survey shows relationship of M-6 to A-6. P.15
- 1979 Detroit Edison shows overlap of sections and township line. P.16
- 1980 Detroit Edison finds A-6, shows relationship to their corridor to East. P.17
- 1982 Detroit Edison survey finds 1/2" iron rod per Act 74 (see P.8). P.18
- 1982 Hughes survey shows M-6 and M-7 relationship with witness'. P.19
- 1984 Boss survey uses corner, shows witness'. P.20
- 1985 Garlock survey shows corner with witness'. P.21
- 1985 Boss survey shows corner with witness'. P.22
- 1988 Garlock survey shows relationship with A-6. P.23
- 1990 Garlock survey shows corner and witness". P.24-24A
- 1993 Hughes survey shows relationship with A-6. P.25-25A
- 1995 Hughes survey shows relationship with A-6. P.26-26A
- 1996 Boss survey shows corner with 1971 witness'. P.27-27A
- 1997 Hughes witness comparison list. P.28-28B