

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9

For corners in

Livingston
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>2N</u> R <u>3E</u> | <u>M-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

DEC 22 10 13 AM '93
 NANCY HAVILLAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

FILED

L.S.C. # 80m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Darrell D. Hughes, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO: 1825
 Aspen 16" N71W 72 lks.
 Aspen 18" S79W 150 lks.

REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 1993
 COMMISSION

* Additional historical information on back of sheet:

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Fd. 1/2" iron rod 1' east of centerline of Dutcher Road

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-11, T2N, R3E, IOSCO, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.
 037 DEG. 34.11' SET NAIL/TAG W/S 40" OAK
 148 DEG. 19.20' SET NAIL/TAG W/S 12" WILLOW
 171 DEG. 52.63' SET NAIL/TAG W/S 20" WILLOW
 176 DEG. 72.22' SET NAIL/TAG W/S 30" OAK
 005 DEG. 64.00' FD. 1/2" IRON ROD

Signed by: Darrell D. Hughes Approved by Liv. Co. Peer Group: Nov. 17, 1993
 Date: 12-21-93
 Surveyor's Michigan License No. 19834

IOSCO TOWNSHIP, T2N, R3E

M-11, NORTHEAST CORNER SECTION 36

FIELD 11-06-1993 D.D.HUGHES AND ASSOCIATES

Found 1/2" iron rod 1' east of centerline Dutcher Rd., 0.1' below grade, 36.80' south found 1/2" iron rod for A-11, Marion, Twp. North 64.00' fd. 1/2" iron rod.

1825. corner first set by Sylvester Sibley, Deputy U.S. Surveyor. Later falling for A-11, Marion shows 56 links (36.96' south)

1861, Ezra Fairchilds, subdivides Section 36, shows 1/4 line measure.

1878, Isaac Teller, County Surveyor subdivides Sec. 30, Marion, sets A-9 and A-11 ".....located by closing distance to Iosco Twp. Sec. 36"

1915, Grant Dunning shows falling distance as 56 links (36.96').

1918, Grant Dunning subdivides Sec. 36, Iosco Twp., ".....set Northeast corner 80.19 chains north of Southeast corner."

1963, Charles Garlock sets 1/2" X 16" iron at fence line West for NE corner Sec. 36.

1971, Henderson and Bates shows closing distance of 100.8' in survey of Section 30, Marion for Detroit Edison. Set SW of Sec. 30, Marion. Found SE 25, Iosco.

1976, Oscar Boss, "....set 1/2" iron on line with NW corner and West 1/4 corner Section 31, Marion, 36.96' North of the West 1/4 corner (government deflection)" Files Act 74, LSC no. 948.

1986, Garlock uses Boss corner for NE Sec 36.

1990, Matthew Brady uses same corner, sets new witness'

64 feet north of this point is an iron set by Garlock and used by Benton and Henderson and Bates at occupation line to West. Most surveyors are not using this point now.