

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 22 10 13 AM '93
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

FILED

For corners in

Livingston
(County)

Located In:

Corner Code #/

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>2N</u> R <u>3E</u> | <u>M-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling In Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

L.S.C. #79m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Darrell D. Hughes, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO: 1825
 Black Oak 14" N45W 90 lks.
 White Oak 19" N31E 62 lks.

RECORDS & REVISIONS
 1993
 COMMISSION

* Additional historical information on back of sheet:

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Fd. 1/2" iron rod (no ident. cap) 4' west of west edge 20 ft. wide gravel road

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-12, T2N, R3E, IOSCO, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.
 358 DEG. 38.04' SET NAIL/TAG E/S 26" OAK
 215 DEG. 7.93' SET NAIL/TAG E/S 15" OAK
 045 DEG. 44.92' SET NAIL/TAG NW/S TWIN 10" CHERRY
 155 DEG. 54.15' SET NAIL/TAG W/S 24" OAK
 180 DEG. 36.09' SET NAIL/TAG E/S 28" OAK

Signed by Darrell D. Hughes Approved by Liv. Co. Peer Group: Nov. 17, 1993
 Date 12-21-93
 Surveyor's Michigan License No. 19834

IOSCO TOWNSHIP, T2N, R3E

M-12, EAST 1/4 CORNER SECTION 36

FIELD 10-26-1993 D.D.HUGHES AND ASSOCIATES, FOWLerville

Found 1/2" iron rod, (no ident. cap) 4' west of west edge 20 ft. wd. gravel road and 26.50' north of found 3/4" iron pipe for west 1/4 corner Sec. 31, Marion Twp. (A-12).

1825, corner first set by Sylvester Sibley, Deputy U.S. Surveyor.

1861, Ezra Fairchilds, subdivides Section 36, shows 1/4 line measures.

1915, Grant Dunning shows falling of 28 links (18.48') with A-12 Marion.

1918, Grant Dunning sets stone 40 chains north of SE cor. Sec. 36, Iosco.

1950, Clay Gordon refers to corner in NE1/4 Sec. 36 survey. Did not say what was found or what was set. No witness'.

1976, Oscar Boss sets 1/2" iron rod on line with NW cor. and West 1/4 corner Sec. 31, Marion. and at fence post hole (26.50' North of West 1/4 cor.). Files Act 74 for this corner (LSC 948) and for A-12 (LSC 950), Marion Twp. showing relationship of corner falling.

1978, Gary Boss uses same corner in NE 1/4 Sec. 36 Survey, L.912, P. 252.

1979, Charles Garlock uses corner in survey, L.968, P.222.

1979, Larry Bryan uses corner in survey, referencing LSC 948.

1980, Gary Boss, uses same corner again, shows falling relationship.

1986, Garlock shows same corner in survey for NE1/4 Sec. 36, Iosco.

1989, Gary Boss shows corner in survey SW1/4 Sec. 31, Marion.

1990, Matthew Brady uses same corner in NE1/4 Sec. 36, Iosco survey.

Surveyors, in recent, have been using same point, as set by Boss in 1976, for corner. Point is tree covered and at West edge gravel road (Dutcher). Measures by different surveyors to M-11 and M-13 agree.