

9-

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T2N R 4E C-13  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

1997 AUG 19 A 10:03

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C.# 684m  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CHARLES E. GARLOCK, in a field survey on AUGUST 9, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN  
GLO WITNESSES: WO 14"-N28E-210 LKS  
BO 18"-N32W-184 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" I. ROD WITH BOSS CAP ON TOP AT THE NORTHERLY FACE OF A 30" OAK, OLD FENCE IN TREE RUNNING EAST, WEST AND SOUTH, NO OCCUPATION TO THE NORTH, FOUND NO OTHER IRONS IN THE AREA, POINT MAY BE USED AS A COMMON CORNER WITH T1N-R4E

SURVEY &  
REMONUMENTATION

FEB 24 1998

SECTION

P.A. 345 1980, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 2/26/97 CO. REP JED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-13: SE CORNER SEC. 31 T2N-R4E, MARION TWP. LIV. CO. MI, RESET POINT WITH 1 1/4" X 36" I. PIPE WITH LIV. REMON BRASS CAP ON TOP AT +0.5'  
EAST-15.92'-SP & TAG N/S 18" OAK  
N50W-31.00'-SP & TAG N/S 14" MAPLE  
N30W-45.49'-SP & TAG E/S 16" MAPLE  
WEST-37.33'-SP & TAG N/S 7" ELM  
FOUND NO CORNER FOR T1N-R4E



Signed by Charles E. Garlock Date AUGUST 10, 1997  
Surveyor's Michigan License No. 14762

SERVING LIVINGSTON COUNTY  
SINCE 1869

*"Be Sure of Your Ground"*

**CHARLES E. GARLOCK**  
PROFESSIONAL SURVEYOR  
705 N. MICHIGAN AVE.  
HOWELL, MICHIGAN 48843  
OFFICE: (517) 546-3340  
FAX: 517 546-2941

FEBRUARY 18, 1997

**CORNER SUMMARY**

C-13: SOUTHEAST CORNER OF SEC 31 T2N-R4E, MARION TWP. LIV. CO. MI  
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO  
WITNESSES REMAIN.

FAIRCHILDS 1839 WITNESS IS GONE.  
BOSS FOUND A 1/2" IRON ROD AT THE NORTH BASE OF A 30" OAK AS DID  
BENTON IN '74, HUGHES '95 AND GARLOCK IN '96 & '97; ALL WITNESSES  
BY THE ABOVE SURVEYORS WERE FOUND AND CHECKED. WE FOUND THE 1/2"  
IRON ROD ON THE NORTH SIDE OF A 30" OAK WITH REMAINS OF A FENCE EAST,  
WEST AND SOUTH, NO OCCUPATION TO THE NORTH NEAR BY. GLO JOG IS 5.28  
EAST BUT THE CORNER APPEARS TO BE OCCUPIED AS COMMON WITH PUTNAM TWP.  
MEASURES WEST ARE: 2610.96=FAIRCHILD 1851, 2649.68=BENTON '84,  
2649.55=HUGHES '95 AND 2649.53 = GARLOCK '96 & '97. MEASURES EAST  
ARE: 2659.76=BENTON '74, 2659.37=BENTON '84 AND 2659.40=GARLOCK '96  
& '97. CORNER IS IN A DENSE WOODS AND NOT GOOD FOR GPS. RECOMMEND  
CONTINUED USE OF THE CORNER AS FOUND.



CHARLES E GARLOCK  
PS 14762  
MAR97C13

SUCCESSOR TO:

W. BULLOCK, L (1844 TO 1926) GRANT H DUNN, P.E. (1865 TO  
CLAY W. GORDON, RLS (1883 TO 1970) LYLE W. MUNSELL, RLS (1904 TO 1987)