

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 MAY 21 A 9:23

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T2N R4E</u>	<u>H-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C.#1022m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, JACK K SMITH, in a field survey on APRIL 30, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1825 SIBLEY SET POST  
BLACK OAK 7 N 1/2° E 65.3'  
WHITE OAK 10 S 19° W 44.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" OD PIPE 6' WEST OF A NEW FENCE LINE IN OLD FENCE TO EAST. THIS POSITION IS THE ONLY ONE THAT APPEARS TO HAVE BEEN USED.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 SOUTH 1/4 CORNER SECTION 27 AND NORTH 1/4 CORNER SECTION 34, T2N, R4E, MARION TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:  
SET 1 1/4" X 36" STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 1/2 FOOT ABOVE THE SURFACE OF SURROUNDING GROUND.

N88°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN SOUTH SIDE 16" OAK 18.62'  
S85°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN SOUTH SIDE 7" OAK 19.26'  
S12°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN WEST SIDE 9" OAK 36.35'  
N05°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN EAST SIDE 9" CHERRY 24.63'  
S30°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN WEST SIDE 5" OAK 29.82'

Signed by: [Signature] Date 5-10-1999



Surveyor's Michigan License No. 35999