

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2N R 4E I5
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

9/

1998 AUG 20 P 4:46

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #891m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

CHARLES E GARLOCK, in a field survey on AUG 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:
 GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY
 GLO WITNESSES: W020-S38W-332 LKS
 B ASH 8-N33½E-276 LKS



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND VERY OLD CORNER POST WITH REMAINS OF FENCE LINES TO THE NORTH, EAST & WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I5: NE COR. SEC. 15, T2N-R4E, MARION TWP. LIV. CO. MI; REPLACED FENCE POST WITH 1 1/4" X 36"
 I. PIPE WITH LIV. CO. REMON BRASS CAP ON TOP. AT +0.8'
 N29W-97.23'-SP & TAG W/S 8" ELM
 S52W-37.82'-SP & TAG E/S 12" ELM
 S60E-49.30'SP & TAF E/S 7" ELM
 N35E-97.86'-SP & TAG W/S 6" ELM
 DROVE CARSONITE POST ALONG SIDE

Signed by Charles E. Garlock
 Surveyor's Michigan License No. 14762

Date August 17, 1998

PA. 248 1990, APPROVED BY LIVINGSTON COUNTY
 PEER GROUP ON 5-20-98, CO. REP. JED