

SURVEY & REMONUMENTATION

FEB 25 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

SECTION
For corners in

LIVINGSTON

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------------------|-----------|
| 1. Public Land Survey | T <u>2</u> N R <u>4</u> E | <u>I6</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

9/ 1998 AUG 20 P 4: 46
NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #889m

Register of Deeds Stamp & File Number


4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, C HARLES E GARLOCK, in a field survey on AUG. 6 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY
GLO WITNESSES: TAM 14- N73W-34 LKS
TAM 10- S89E-37 LKS



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" I. ROD, IRON APPEARS TO FIT OCCUPATION BY FALLING IN E-W FENCE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I6: W 1/4 COR. SEC. 15 T2N-R4E, MARION TWP. LIV. CO. MI, REPLACED 1/2" I. ROD WITH 1 1/4" X 36" PIPE WITH LIV. CO. REMON BRASS CAP ON TOP
N8W-7.59'-SP & TAG 14" BIRCH
S70E-13.08'-SP & TAG 6" MAPLE
S76W-21.62'-SP & TAG 10" ASH
S26W-27.42'-SP & TAG 12" ASH

Signed by Charles E. Garlock Date AUGUST 8, 1998
Surveyor's Michigan License No. 14762

PA. 345 1960, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 8/5/98, CO. REP JED