

**SURVEY & REMONUMENTATION**

FEB 25 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**FILED**

**SECTION**

For corners in

LIVINGSTON Located In: Corner Code #  
(County)

1. Public Land Survey T 2 N R 4E 18  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

91  
1998 AUG 20 P 4:46  
NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843  
L.S.C. #894m  
Register of Deeds Stamp & File Number


4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

CHARLES E GARLOCK, in a field survey on AUG. 10, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
GLO SURVEY DATED: APRIL 15, 1825, BY S SIBLEY  
GLO WITNESSES: TAM 6- S53W-130 LKS  
TAM 10-N34E-60 LKS

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FD. 1/2" I. ROD W/BOSS CAP, EXISTING FENCES IN 3 DIRECTIONS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
I8: E1/4 COR. SEC. 22 T2N-R4E, MARION TWP. LIV. CO. MI, REPLACED 1/2" I. ROD WITH 1 1/4" X 36" PIPE WITH LIV. CO. REMON BRASS CAP ON TOP.  
S65E-70.63'-SP & TAG W/S DBL 14" MAPLE  
S10W-25.32'-SP 7 TAG E/S 14" TRIPLE MAPLE  
S41W-20.61'-SP 7 TAG E/S 20" MAPLE  
NORTH-4.15'-SP & TAG E/S 14" TRIPLE MAPLE

Signed by Charles E. Garlock Date AUGUST 12, 1998  
Surveyor's Michigan License No. 14762

PA. 348 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 8/5/98 CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1985