

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2N R 4E I 10
- T ___ R ___ _____
- T ___ R ___ _____
- T ___ R ___ _____
- 2. Property Controlling S ___ T ___ R ___ _____
- in Section S ___ T ___ R ___ _____
- 3. Miscellaneous S ___ T ___ R ___ _____
- Property in Sec. S ___ T ___ R ___ _____

91 1998 AUG 20 P 4:46

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #897m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

CHARLES E GARLOCK, in a field survey on AUG 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY
GLO WITNESSES: W010-S86E-42 LKS
 W010-S54E-114.LKS.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ROTTED REMAINS OF FENCE POST WITH FENCE LINES TO THE NORTH, SOUTH, EAST AND WEST., STONES RING THE FENCE POST HOLE. SINCE WE FIRST VIEWED THIS CORNER IN EARLY 1998, A CONCRETE MONUMENT FOR SOUTHWEST CORNER OF "SUNDANCE MEADOWS" HAS REPLACED THE ROTTED REMAINS OF THE CORNER POST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I10: W 1/4 COR. SEC. 26, T2N-R4E, MARION TWP. LIV. CO. MI, SET REMON BRASS CAP ON TOP OF 4" CONCRETEMON. WHICH WAS SET SINCE WE FIRST RESEARCHED THIS CORNER.
WEST-19.80'-SP & TAG N/S 12" CHERRY
N40E-11.47'-SP & TAG E/S 12" CHERRY
EAST-18.57'-SP & TAG N/S 36" HICKORY
S25W-25.52'-SP & TAG E/S 12" HICKORY

Signed by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date AUGUST 12, 1998