

DEC 13 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston  
(County)

Located In:

Corner Code ##

- |                                       |                         |             |
|---------------------------------------|-------------------------|-------------|
| 1. Public Land Survey                 | T <u>2N</u> R <u>4E</u> | <u>I-12</u> |
|                                       | T _____ R _____         | _____       |
|                                       | T _____ R _____         | _____       |
|                                       | T _____ R _____         | _____       |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____       |
|                                       | S _____ T _____ R _____ | _____       |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____       |
|                                       | S _____ T _____ R _____ | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                         |             |
| 5. Private Claims _____               |                         |             |

RECORDED  
FILED  
 Nov 29 3 37 PM '93  
 NANCY HAVILAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843

L.S.C.#46m

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34	●	35		36		
13													

I, Darrell D Hughes in a field survey on October 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey date: April 15, 1825  
 GLO witnesses: W0 10-N35E-.18 ch  
 W0 12-S20½W-.38 ch

See additional historical data on rear of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Axle shaft with 4" dia. gear on top.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

W ¼ corner Section 35, T2N-R4E; witnessed the found Axle shaft w/4" dia. gear on top.  
 North-19.68'-sp E/s 10" Oak  
 N45W-27.29'-sp N/s 15" R Oak  
 N80W-37.86'-sp N/s 12" R Oak  
 S50W-22.40'-sp S/s 12" R Oak  
 S30W-23.30'-sp E/s 13" R Oak  
 East-11.34'-sp N/s 17" R Oak

Signed by Darrell D Hughes  
 Surveyor's Michigan License No. 19834



Approved by Liv. Co. Peer Group: Oct. 30, 1993  
 Date 11-29-93

October 23, 1993

I-12: W 1/4 Cor. Sec. 35 Marion Twp. Liv. Co. MI

Found axle shaft with gear on top (Model T?) at NW Corner Plat "Log Cabin Park" L2 pg.33 Livingston Co. Records. C.W. Gordon, Co. Surveyor, shows NW Cor. of "Log Cabin Park" to be 1/4 Corner in 1923, but no witnesses. P.L. Benton (date?) and C.E. Garlock (1964) found W 1/4 Cor. to be axle shaft and their witnesses fit same point, if P.L. Benton's witness bearings are rotated 90° clockwise. Found old remains of fence lines running North, East and South and GLO distance South to North side of lake (283.8') fits pretty good; Plat calls for 277.0' to iron set on shore-line and I found this to be true in a 1964 survey. W 1/4 Cor. is located on top of a bank falling sharply to SE and in a woods.

---