

DEC 13 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston (County)

Located In:

Corner Code #/

1. Public Land Survey

T 2N R 4E

I-13

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. Recorded Plat

5. Private Claims

NOV 29 3 37 PM '93
NANCY HAVILLAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

RECORDED
FILED

L.S.C. #47m

Register of Deeds Stamp & File Number

I, Darrell D Hughes, in a field survey on October 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey notes: April 15, 1825
GLO witnesses: Hick 4-N48W-.52 ch
BO 4-N4E-1.48 ch

Additional historical data on rear of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Search of the area found nothing and no known surveys tied to said corner EXCEPT witnesses and a measurement by Miles W Bullock, Co. Surveyor, 1880; N44 1/2 E-.56 ch. (36.96')-W0 4 and measured East 2647.26' to the S 1/4 cor. Sec. 35 T2N-R4E. Found remains of a stump about 18" dia. at approx bearing of N48E (true) and measured 36.96' to a point on existing centerline of Schafer Road. said point lined very good with an existing OLD fence line to the North, meas'd. North 24.75' to the face of an Old corner post of fence line North and roadside fence to the East. Historically Old Roadside fences in Livingston County were built 1 1/2 rods North of Gov't lines. Then measured East 2646.19' to S 1/4 cor. Sec. 35 and compared with Bullock's 1880 measure of 2647.26 feet. Established SW cor. of Sec. 35 at the re-established point.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13: SW cor. Section 35, T2N-R4E, set 1 1/4" X 36" breakaway I. Pipe with Liv. Co. brass cap on top and in a MOn. Box.
North-24.75'-face of OLD wood cor. post and fence line North
N50E-36.96'-ctr. OLD stump (Bullock's 1880 tie)
North-109.72'-sp W/s 12" Cedar
S45E-57.83'-sp N/s 8" Walnut
S20E-90.60'-sp W/s 50" W Oak
S10W-66.02'-sp W/s 16" Cedar
and on ctr. of Schafer Rd.

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

Signed by Darrell Hughes



Approved by Liv. Co. Peer Group: Oct. 30, 1993

Date 11-29-93

Surveyor's Michigan License No. 19834

October 23, 1993

I-13: SW Cor. Sec. 35 Marion Twp. Liv. Co. MI

I did sweep of the area and did not find any irons except an iron for NW Cor. Sec. 2 Putnam Twp. Found very old fence line to the North and a road side fence line at about half the distance of typical Livingston Co. old R.O.W. fences. Also found an 18" stump about N54°E. Therefore by measuring 24.75' ($\frac{1}{2}$ of a 3 rod distance) Southerly from face of post and 36.96' (.56 ch.) from center of 18" stump I found they intersected at a point in line with old fence line to the North and also fell on the existing center line of Schafer Rd. Then measuring East to the S 1/4 Sec. 35 I found the distance to be 2646.19'; Bullock had measured 2647.26' in 1880. Set a temporary PK spike for SW Cor. Sec. 35 which I feel is the correct location based on the above facts and findings. Found no surveys in the area due to large tract ownership. NW Cor. Sec. 2 Putnam Twp. is located 31.00' East and 3.11' South of a line between SW and S 1/4 Cor. Sec. 35. Road surface is asphalt with trees located to the West, Southerly to ESE, open to the North.