

SURVEY & REMONUMENTATION

DEC 13 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code ##

- | | | | | | | |
|------------------------------------|---|-----------|---|-----------|-------------|-------|
| 1. Public Land Survey | T | <u>2N</u> | R | <u>4E</u> | <u>J-11</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

NOV 29 3 37 PM '93
 NANCY HAYLAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

FILED

L.S.C.#48m

Register of Deeds Stamp & File Number

I, Darrell D Hughes, in a field survey on October 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey notes: April 15, 1825
 GLO witnesses: BO 12-N43E-.80 ch
 WO 28-S5E-1.00 ch

Additional historical data on rear of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" I. Rod near surface of road and found second 1/2" I. Rod -2.0' below first iron and located WNW 0.4' from I. Rod at surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11: N 1/4 cor. Sec. 35, T2N-R4E, reset with 1 1/4" X 36" breakaway I. Pipe with Liv. Co. brass cap on top; set new I. Pipe on top of the lower 1/2" I. Rod found and matched older witnesses by L. W. Munsell.
 N10W-28.08'-sp W/s 4" Sassafrass
 N75E-92.38'-sp S/s 16" Poplar
 S45E-53.10'-sp N/s 18" Cherry
 S5E-25.46'-sp W/s 12" Poplar
 N50E-48.75'-ctr. 6" steel post on top of conc. abutment.
 North-1.0±-ctr. of Road
 East-17'±- ctr. of Road to South

Signed by [Signature] Approved by Liv.Co. Peer Group: Oct. 30, 1993
 Date 11-29-93
 Surveyor's Michigan License No. 19834

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

October 23, 1993

J-11: N 1/4 Cor. Sec. 35 Marion Twp. Liv. Co. MI

Found $\frac{1}{2}$: iron rod; earliest known witness 1880 by M.W. Bullock 27.06' to 13" Sassafras in same area, one about 2 feet nearer Cor. and one witnessed at 29.42'. G.H. Dunning's 1919 witness was gone. Sweep of the area found no additional irons. This Corner has been used for surveys in Sec. 35 and 36 by the following: Boss Engineering - 1983, 88; B. Thompson - 1988; P.L. Benton; C.E. Garlock - 1978, 87, 93 and L.W. Munsell - 1954, 64. Act 74 filed by Boss Engineering 1976. Point is near center line of road, fits old occupation to the North and fits West R.O.W. line of private road South. Measures about 2590.45' to NW Cor. and 2587.18' to NE Cor. Area is open to the West and some trees North, South and East. Iron is in gravel road.