

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

Livingston
(County)

Located In:

Corner Code ##

1996 NOV -5 P 2: 11

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>2N</u> R <u>4E</u> | <u>K-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843

L.S.C.#568m
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles E Garlock, in a field survey on October 24, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO survey dated, April 15, 1825 by S Sibley DS
 GLO witnesses: W020-S83W-74 lks
 W026-S03W-180 lks

Additional historical data on rear of sheet

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" I. Rod in 3/4" I. Pipe in Mon. Box in center of Mason and Pinckney Rd. inter-section, the found irons located 0.42 feet South of the East-West Township line and on the Section line between sections 1 and 2, T2N-R4E



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 2-7-96 CO. REP JED

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-1, NW corner Section 1 T2N-R4E, Marion Twp. Liv. Co. MI, set 1 1/4" X 36" I. Pipe on Township line, 0.42 feet North of found 1/2" I. Rod in 3/4" I. Pipe and on line between Sections 1 and 2; with Liv. Co. Remon brass cap on top. Set Amended corner cap on the found 3/4" I. Pipe. Witnesses to set I. Pipe, 1 1/4" X 36"
 N59E-48.88'-face 10" steel post holding signal light cable
 S57W-59.65'-face 10" steel post holding signal light cable
 S33E-79.05'-sp & tag E/s 16" Db1 Elm
 S60W-136.08'- NE corner of brick Gas Station
 West-108.03'-SE corner Sec. 35 T3N-R4E
SOUTH-0.42'- 1/2" I. ROD IN 3/4" PIPE WITH AMENDED MONUMENT CAP. (JED)

Signed by Charles E Garlock Date October 26, 1996
 Surveyor's Michigan License No. 14762

CORNER SUMMARY

K-1: NORTHWEST CORNER, SECTION 1, T2N-R4E, MARION TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN.

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY, DS, AND NONE OF THE
GLO WITNESSES REMAIN.

M W BULLOCK WITNESSED THE CORNER IN 1872, G DUNNING AGAIN IN 1915,
CALLING IT A PLOW POINT WITH STONE, IN 1920 G DUNNING CALLED IT AN
IRON IN THE CENTER OF AN EIGHTEEN FOOT WIDE ASPHALT PAVEMENT (???)
AND 31 FT NORTH OF THE NORTH EDGE OF THE SIDEWALK TO THE SOUTH.
IN 1931 C GORDON NOTED THE CORNER WAS LOCATED THE SAME PLACE AS
DUNNING IN 1920, AS DID L MUNSELL IN 1960. IN 1965 A PIERSON OF
MDOT FOUND A 3/4" PIN AND IN 1975 D HOOTH OF MDOT CALLED IT A 3/4"
I. PIPE IN A MON. BOX, AS DID BENTON IN 1981, CHMP IN 1984 AND
BOSS IN 1986. MEASURES EAST TO THE NORTH 1/4 CORNER ARE 2610.69
FT BY BOSS AND 2609.78 BY MYSELF. MEASURES SOUTH TO THE WEST 1/4
CORNER ARE: 3863.03 FT BY BENTON & MDOT, 3862.78 BY MYSELF,
3862.74 BY MYSELF AND BENTON, 3862.27 AND 3862.36 BY BOSS, 3862.88
BY BENTON AND 3862.27 BY THOMPSON. WEST TO THE NORTH 1/4 CORNER
OF SECTION 2: 2584.0 FT BY C GORDON, 2588.4 AND 2587.3 BY L
MUNSELL, 2591.99 BY CHMP AND 2592.11 BY MYSELF. REMAINING
WITNESSES CHECK TO THE FOUND CORNER AND WE CAN CONFIRM THE CORNER
BACK TO 1915. FOUND A 3/4" I. PIPE IN A MON. BOX, THAT IS 108.03
FT. EAST OF THE SOUTHWEST CORNER OF SECTION 36, HOWELL TOWNSHIP
(GLO IS 107.58) AND 0.42 FT. SOUTH OF THE TOWNSHIP LINE. CORNER
IS IN THE ASPHALT X-ING OF PINCKNEY AND MASON ROADS AND AREA IS
CLEAR FOR GPS. THE QUESTION IS WILL WE BE ABLE TO FIT BOTH IRONS
IN THE MON. BOX OR WILL A SECOND MON. BOX BE NEEDED IN A BUSY
INTERSECTION.



CHARLES E GARLOCK
PS 147862
HOW96K11

2N4E
K1