

SURVEY & REMONUMENTATION

DEC 13 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code #/

1. Public Land Survey	T	<u>2N</u>	R	<u>4E</u>	<u>K-13</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

HANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

NOV 29 3 38 PM '93

FILED

L.S.C.#52m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Darrell D Hughes, in a field survey on October 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO survey notes: April 15, 1825
GLO witnesses: BO 7-N42W-,44 ch
WO 10-N57½E-3.08 ch.

Additional historical data on rear of sheet:


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" I. Rod in Monument Box 12.54' West of NE cor. Section 2 T1N-R4E.
Set by L W Munsell- 1964

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13: SW cor. Section 36, T2N-R4E, reset with 1½" X 36" breakaway I. Pipe with Liv. Co. brass cap on top in found Mon. Box..
N40E-55.18'-sp W/s U Pole
S45W-55.18'-NE cor. Conc. block Bldg. } both distances are the same
N75W-171.68'-sp S/s U. Pole
N40W-79.28'-SE cor. 6" square Steel leg to sign post, most E'ly
East-4.0'±-ctr. Pinckney Rd.
North-4.0'-ctr. W Schafer Rd

Signed by [Signature]
Surveyor's Michigan License No. 19834



Approved by Liv. Co. Peer Group: Oct. 30, 1993
Date 11-29-93

October 23, 1993

K-13: SW Cor. Sec. 36 Marion Twp. Liv. Co. MI

Found $\frac{1}{2}$ " iron rod in Monument Box 12.54' West of NE Cor. Sec. 2 Putnam Twp. (also a $\frac{1}{2}$ " iron rod in Mon. Box). Earliest known witness is 1916 by G.H. Dunning, Co. Surveyor, who was witnessing the NE Cor. of Sec. 2 Putnam Twp. which he stated was 6.5' East of center line of Pinckney Rd., the approximate location of NE Cor. Sec. 2 Putnam Twp. today. For a period of time (1961± to 1963±) L.W. Munsell called this the SE Cor. Sec. 35 Marion Twp. But when the Mon. Boxes and irons were set at the time Pinckney Rd. was re-surfaced in the mid-1960's he found the error and set the Corner correctly 12.54' West of NE Cor. Sec. 2 Putnam Twp., which is also the GLO jog. Since that time the following known surveyors have used the Corner as set: A.F. Miller, P.L. Benton, Boss Engineering, D. Hughes, L.W. Munsell and C.E. Garlock. Act 74's filed by Miller 1977 and Garlock 1973. Sweep of area found no additional irons. Trees located in SE quadrant and clear in the balance except for Shell gas station sign. Road surface is asphalt.