

FILED

19

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 MAY 9 11 03 AM '95

For corners in

Livingston (County)

Located In: Corner Code M-6

NANCY HAVILAND REGISTER OF DEEDS LIVINGSTON COUNTY, MI 48843

- 1. Public Land Survey T 2N R 4E M-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

C.L.S.# 399m

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (6,13) contains a small circle.

Charles E. Garlock, in a field survey on April 28, 1995, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration: GLO survey dated April 15, 1825 by Sibley DS GLO witnesses: W012-N47W-391ks W016-S45 1/2 W-35 1ks

Additional historical data on rear of sheet Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found Railroad spike

Commission stamp: STATE OF MICHIGAN COMMISSION APR 28 1995

Description of monument for corner and accessories established to perpetuate locating the position of the corner: M-6: East 1/4 corner Section 13 T2N-R4E, Marion Twp. Liv. Co. MI, reset RR spike with 1 1/4" X 36" breakaway I. Pipe with Liv. Co. Remon brass cap on top at -0.5' N35E-50.37'-sp & tag w/s U. Pole N30W-56.14'-sp & tag East/s 40" oak S75W-24.50'-sp & tag E/s 38" oak S20E-124.97'-sp & tag NE/s 18" Hickory East-2'±-c/l Fisk Rd. North-337.49'-W 1/4 cor. Sec. 18 T2N-R5E



Signed by Charles E. Garlock Date April 29, 1995

Surveyor's Michigan License No. 14762

CORNER SUMMARY


M-6: E 1/4 COR. SECTION 13, T2N-R4E, MARION TWP., LIV. CO. MI

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY, NONE OF THE GLO WITNESSES REMAIN.

M BULLOCK WITNESSED THE CORNER IN 1904, NONE OF THE WITNESSES REMAIN. NEXT KNOWN ACTIVITY WAS IN 1980 WHEN I FOUND A RR SPIKE ABOUT 2 FT. WEST OF THE CENTERLINE OF A GRAVEL ROAD. SINCE THAT TIME ALBRIGHT, DESINE, THOMPSON AND MYSELF HAVE FOUND THE RR SPIKE AND ALL OF OUR WITNESSES CHECK. NO OCCUPATION TO THE WEST UNTIL 1/4 MILE AND THEN IT LINES WITH A FENCE LINE TO THE CENTER OF SAID SECTION. GLO DISTANCE NORTH TO THE GENOA CORNER IS 322.41 FEET AND IT MEASURES 337.49 FEET TO AN IRON AND OCCUPATION TO THE EAST. MEASURE NORTH TO THE NE COR. IS: 2636.71 FT. = DESINE AND MYSELF; SOUTH TO THE SE COR.: 2645.99 FT = THOMPSON, 2645.78 = DESINE AND 2645.80 = MYSELF. MEASURE WEST TO THE CTR. OF SECTION : 2525.08 FT. = DET. EDISON & ALBRIGHT; 2524.48 = DESINE AND 2524.77 = MYSELF. TWO ACT 74'S ARE RECORDED AND ONE ACT 132. OVERHANGING TREES MAKE THIS A POOR GPS STATION.

Charles E. Garlock

CHARLES E GARLOCK
PS14762



TN-4E
ML