

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>34</u> T. <u>2</u> N. <u>5</u> E.	<u>2</u> S. R. <u>5</u> E.	<u>13 H</u>
2. PROPERTY CONTROLLING IN SECTION <u>34</u> T. <u>2</u> N. <u>5</u> E.	<u>2</u> S. R. <u>5</u> E.	
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ E.	_____ S. R. _____ E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

LIVINGSTON CO  
GENDA TWP.  
BRIGHTON E.A.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, D. SCOTT do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on SEPT. 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on SEPT. 1972, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

FOUND 1" IRON PIPE WITH BRASS CAP, RECOVERED FROM WITNESSES BY W. LEE PADDISON R.L.S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" IRON PIPE WITH BRASS CAP  
N 60° W 47.2' W. GATE POST  
S 69° W 50.4' 12" TWIN OAK  
S 25° W 17.5' 30" OAK  
N 50° E 14.6' 14" OAK  
S 45° E 25.0' & ROAD ON CURVE  
ALL DISTANCES ARE MEAS. TO P.K. NAILS IN THE BASE OF TREES

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_