

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in  
LIVINGSTON  
(County)

Located in: GENOA Corner Code #

9

1999 NOV 22 A 11:07

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC# 1100m

Register of Deeds Stamp and File Number

- 1. Public Land Survey T 2N R 5E D-9
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

I, Bryan L. Boss, in a field survey on JUNE 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


SET POST  
12" TAMARACK S52°E 2.66 CHAINS  
14" B. OAK N85°E 8.2 CHAINS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON PIPE IN E'LY R.O.W. FENCE OF RAILROAD, FENCE RUNS NORTH & SOUTH

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1 1/4" X 3/8" PIPE WITH BRASS CAP  
STAMPED "LIVINGSTON COUNTY  
REMONUMENTATION CORNER"  
N05°W 31.29' SET REMON NAIL AND TAG W/SIDE  
18" CHERRY  
N60°W 130.18' SET REMON NAIL & TAG E/SIDE  
P. POLE  
DUE EAST 13.76' SET REMON NAIL AND N/SIDE  
22" OAK  
S20°W 100.27' SET REMON NAIL AND TAG E/SIDE  
P. POLE



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 5-19-99, CO. REP JED

Signed by *Bryan L. Boss*

Date NOV. 9, 1999

Surveyor's Michigan License No. 29238