

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9
FILED

For corners in

Livingston County

Located In:

Corner Code //

1. Public Land Survey	T	<u>2N</u>	R	<u>5E</u>	<u>G-12</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

1998 OCT 22 P 1:19

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC959M
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Bryan L. Boss, in a field survey on Oct. 2, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner set 1823 S. Sibley, Deputy Surveyor, Set Post
W. Oak 12" S.9W. 36 links
B. Oak 12" N.10E. 36 links


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1/2" I rod on easterly
Face of a steep slope. 70'
S. of a East West Fence
no visible occupation

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 9-16-98, CO. REP. JED

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

Set 1 1/2" by 36" long Steel Pipe W/Brass Cap Stamped
"Livingston County Monumentation Corner."
N. 30°E.-90.52 Remon. n/t. W. side Twin 6" cedar
S. 10°E.-12.98 Remon. n/t W. side Twin Autumn Olive
S. 70°W.-4.12 Remon. n/t. S. side 3" Oak
N. 30°W.-24.29 Remon. n/t. W. side 3" Cherry



Signed by [Signature]
Surveyor's Michigan License No. 29238

Date 10-14-1998