

DEC 29 11 25 AM '93

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
LIVINGSTON COUNTY, MI  
48843

For corners in

Livingston Located In: Corner Code #/

1. Public Land Survey T 2N R 5E I-11  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

L.S.C. #171m  
Register of Deeds Stamp & File Number

I, Bryan Boss, in a field survey on December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Unknown

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

SURVEY &  
REMONUMENTATION

1993

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rerod in Monument Box


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Brass Cap Marked: Livingston Co.  
Mon. Corner on 1/2" Rebar

North 27.93' Spike E/Side 40" Oak  
N80°E 112.70' Spike S/Side 50" Oak  
N85°W 130.65' Spike S/Side 36" Oak

Approved by Livingston Co.  
Monumentation Peer Group  
on December 1, 1993

Signed by [Signature]  
Surveyor's Michigan License No. 29238



December 28, 1993

**BOSS ENGINEERING**  
**ENGINEERS & SURVEYORS**

December 1, 1993

SUMMARY

I-11 Northwest Corner, Section 35, Genoa Township  
Livingston County, Michigan


Monument box with Boss capped iron 13.5 feet West of centerline of Timberling Drive/Forest View Estates No. 1 to South. Location is center of Brighton Road in 1967 Munsell/Garlock set railroad spike (see Page 13) on 5-28-81. Boss Engineering Job #81023 found railroad spike per Plat of "Forest View Estates."

On 8-18-92 Boss Engineering set iron in monument box from previous witnesses.

Witnesses found 11-93.

New Power Pole S.E. Quad.  
New Power Pole S.W. Quad.  
40" Oak N/E/S 27.93 North  
50" Oak N/S/S 112.70 N80°E  
36" Oak N/S/S 130.65 N85°W

File: REMON1



A handwritten signature in cursive script, appearing to read "Bryan L. Boss", written over the bottom portion of the professional seal.

①