

**SURVEY &  
MONUMENTATION**

OCT 26 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

9-

NANCY HAVILAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843  
 OCT 4 3 29 PM '95

REFILED

For corners in

Livingston <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>2N</u> R <u>5E</u>	<u>J-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

L. S. C. #461m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

7. Bryan Boss, In a field survey on 8-10, 1995,  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.

8. Description of original monument and accessories and/or subsequent restoration:

Set post at average distance on traverse line  
 for 1/4 section corner.

- White Oak 10" S 19 1/2 E 69 links
- White Oak 8" N 7 E 1.17 chains
- Hickory 6" S 53 3/4 W 38

9. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 3/4" iron found on centerline Crooked Lake Road  
 extended and tree row South.
- South 21.33' spike 24" Oak
- N 55 W 52.40' spike 14" Oak
- West 39.97' 1/2" iron rod in fence
- Northeasterly 66.44' nearest edge of pavement

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 36" pipe 6" deed with brass cap
- 5.93 N 45° E nail & tag East side 6" Poplar
- 21.46 South nail & tag West side 24" Oak
- 21.32 West Northerly "Road End" sign
- 39.46 West Garlock iron in fence
- 52.20 N 55° W nail & tag North side 14" Oak



signed by Bryan L. Boss Date Sept. 28, 1995  
 Surveyor's Michigan License No. 29238

SUMMARY

J-7

North  $\frac{1}{4}$  Corner, Section 23, T2N-R5E, Genoa Township, Livingston County, Michigan.

Found  $\frac{3}{4}$ " iron in I-96 Expressway right-of-way on line with Crooked Lake Road extended and tree row Southerly.

Measured to Witnesses found. M.D.O.T witnesses check (page 16B). Charles Garlock Witnesses (page 17, 19, 20, 24) check. Boss Engineering survey (page 21A) witnesses check. All surveys in dossier use this point.

Boss Engineering Witnesses on Act 74 (L.S.C. No. 1070) are for L-7, North  $\frac{1}{4}$  Corner of Section 24, T2N-R5E or T2N-R6E. (see page 12). Pat Benton Witnesses (page 14) are in Oceola Township, Section 4, but legal description is in Genoa Township.

Note distances on M.D.O.T. maps pages 15, 16 are measured to East bound I-96 construction centerline. After inserting the 126.05 feet difference on page 6, the overall distance between section corners are more in line with measured  $\frac{1}{2}$  miles by Charles Garlock and Boss Engineering.

This Corner has over hanging branches which will not be conducive for G.P.S..

Conclusion:

We find that the Witnesses found on Charles Garlock Survey (page 24. dated May 7, 1994 should be held and pipe set accordingly.

GENJ-7S



*Bryan L. Boss*