

1996 NOV 25 A 9:39

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in GENOA TWP.

<u>LIVINGSTON</u> (COUNTY)	Located In	Corner Code #
1. Public Land Survey	T2N R5E	K-2
	T__ R__	_____
	T__ R__	_____
	T__ R__	_____
2. Property Controlling in Section	S__ T__ R__	_____
	S__ T__ R__	_____
3. Miscellaneous Property in-Sec.	S__ T__ R__	_____
	S__ T__ R__	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

L.S.C. #607m

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BRYAN L. BOSS in a field survey on OCTOBER 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 CORNER SET IN 1823 BY SYLVESTER SIBLEY
 WHITE OAK 30" S 55° W 16
 WHITE OAK 10" N 55° E 4


B. Description of corner evidence found and/or applied in restoring or reestablishing corner:

BOSS ENGINEERING SET CORNER FOR "K-2" BY EXTENDING A STRAIGHT LINE FROM "K-3" NORTHERLY THROUGH A POINT 33.00 FEET WEST OF A CONCRETE MONUMENT AT RIGHT-OF-WAY CORNER 330.00 FEET SOUTHERLY OF "K-2". FITS OCCUPATION FOR CENTERLINE OF KELLOGG ROAD AND FENCE ROWS EAST AND WEST.

C. Description of monument for corner and accessories established to perpetuate location the position of the corner:

SET 1 1/4 X 30" PIPE 1 FOOT BELOW GRAVEL SURFACE WITH A 6" BREAKAWAY AND BRASS CAP STAMPED "LIVINGSTON COUNTY MONUMENTATION CORNER".

N 45° E NAIL & TAG WEST SIDE 4" ASH 23.76
 S 70° E NAIL & TAG WEST SIDE 16" OAK 32.33
 S 10° W NAIL & TAG EAST SIDE ELM 40.12
 WEST NAIL & TAG NORTH SIDE UTILITY POLE 55.41



Signed by Bryan L. Boss Date 11-12-1996
 Surveyor's Michigan License No. 29238

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

SUMMARY

K-2

West 1/4 corner, Section 1, T2N-R5E, Genoa Township, Livingston County, Michigan.

CORNER EVIDENCE

The original Corner was set on May 5, 1833 by Sylvester Sibley (see page 7), and Adams surveyed and witnessed Section 1 in 1838.

Found capped Boss Iron in centerline of Kellogg Road 1/2 foot below gravel surface, in Centerline of Kellogg Road. Also found Cornerstone witnesses to a point 4.6 feet West of Boss Iron. No other evidence or monumentation at this location.

This corner is open for G.P.S.

DISTANCES

On March 13, 1986 Patrick L. Benton surveyed Section 2 (see field notes page 10 and calculation sheet page 11).


December 22, 1989, Cornerstone Surveying (page 12 & 13) found flagging and nail at the ??? East 1/4 corner of Section 2 ???, this point was Traverse Point "P" of Benton survey.

July 9, 1990, Boss Engineering (page 14 & 15) found above mentioned Traverse Point "P" of Benton Survey.

Boss set Corner for "K-2 " by extending a straight line from "K-3" Northerly through a point 33.00 feet West of a concrete monument at R/W Corner 330.00 feet Southerly of "K-2" (circled point on page 14, the origin of this previous survey was not determined). This new location for "K-2" is 4.6 feet East of Traverse Point "P" and fits occupation for Centerline of Road and Fence Rows East and West.

RECOMMENDATION

We recommend acceptance of corner as surveyed by Boss Engineering on March 13, 1996.


Bryan L. Boss No. 29238

