

1996 NOV 25 A 9:39

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in GENOA TWP.

LIVINGSTON  
(COUNTY)

Located In

Corner Code #

1. Public Land Survey

T2N R5E

K-3

T\_\_ R\_\_

T\_\_ R\_\_

T\_\_ R\_\_

2. Property Controlling  
in Section

S\_\_ T\_\_ R\_\_

S\_\_ T\_\_ R\_\_

3. Miscellaneous  
Property in Sec. :

S\_\_ T\_\_ R\_\_

S\_\_ T\_\_ R\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

L.S.C.#605m

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BRYAN L. BOSS in a field survey on OCTOBER 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER SET IN 1823 BY SYLVESTER SIBLEY  
BLACK OAK 8" N 19° E 11  
BLACK OAK 6" N 13° W 11

B. Description of corner evidence found and/or applied in restoring or reestablishing corner:

FOUND 5/8" IRON 1 FOOT ± BELOW GRAVEL SURFACE.  
POINT IS ON LINE WITH FENCE LINE SOUTH

C. Description of monument for corner and accessories established to perpetuate location the position of the corner:

SET 1 1/4" X 30" PIPE 1 FOOT BELOW GRAVEL SURFACE WITH A 6" BREAKAWAY AND BRASS CAP STAMPED "LIVINGSTON COUNTY REMONUMENTATION CORNER"

N 60° W NAIL & TAG SOUTH SIDE 26" HICKORY 76.54  
N 50° E NAIL & TAG SOUTHEAST SIDE ANCHOR POST 46.85  
S 20° E NAIL & TAG WEST SIDE 12" ASH 36.81  
S 45° W NAIL & TAG NORTH SIDE 14" ASH 44.13



Signed by Bryan L. Boss  
Surveyor's Michigan License No. 29238

Date 11-12-1996

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 9-18-96, CO. REP VED

**SUMMARY**  
**K-3**

Northeast Corner, Section 11, T2N-R5E, Genoa Township, Livingston County, Michigan.

**CORNER EVIDENCE**

Found 5/8" iron 1 foot ± below gravel surface. Six (6) feet ± East of centerline of Kellogg Road (Road is Northerly) 3 feet ± North of the centerline of McClements Road (Road is East and West), Point is on line with fence line to South.

Clean Sweep of area produced No Other corners monumented. The intersection of roads is open for G.P.S.


**WITNESSES**

The No. 2 witness, (Railroad spike in South side of 36" Oak) logged by Oscar Boss in 1974, was found on September 12, 1996 (see pages 7 and 23). In review of witnesses, this point is the same point as used in all surveys, this dossier.

**DISTANCES**

The recorded distance of 1336.62 feet to North 1/8 corner (see Pat Benton 1977 survey on page 15) was surveyed previously by William Boyd (per Benton Survey). This distance was confirmed by Boss Engineering July 15, 1995 survey on page 21, this dossier.

We recommend acceptance of corner as found and witnessed as the Northeast corner, Section 11.

  
Bryan L. Boss No. 29238

