

SUMMARY
F-13

South 1/4 Corner, Section 33, Genoa Township.

In December 1815, Alex Holmes set post at 40 chains and recorded one witness.

On 9-17-1948, S.V. Higgins of the Department of Natural Resources surveyed from South 1/4 Corner and set 3/4" Inch pipes in creek and in Chilson Road.

A dam has been constructed between 1950 and the present, North of F-13 approximately 1300 feet \pm . The existing Chilson pond now covers this area and upstream into Section 4, Hamburg Township, about 1/2 mile.

This is now a lost corner.

We recommend setting reference monuments East and on line with the approved Southeast Corner of Section 33 and West and on line WITH the approved Southwest Corner Section 33, at the split distance. Bearings AND distances to be recorded on Act 74 with submission of dossier.



Bryan L. Boss