

MAR 17 2000

SECTION

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11: 08

HANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

For corners in
LIVINGSTON
(County)

Located in: BRIGHTON Corner Code #

9

- 1. Public Land Survey T 2N R 6E C-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

LSC# 1107m

Register of Deeds Stamp and File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Bryan L. Boss, in a field survey on 10-12-99
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


SET POST
OAK 12" S 16° W 32 LINKS
OAK 10" N 17 1/2° W 86 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" POST
0.50' SOUTH 0.00' WEST OF FENCE POST

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1 1/4" X 3/8" PIPE WITH BRASS CAP STAMPED
"LIVINGSTON COUNTY REMONUMENTATION
CORNER"
NORTH 32.40' REMON NAIL & TAG W/S TWIN 25"
OAKS
WEST 53.20' REMON NAIL & TAG S/S 30" OAK
S 30°W 23.90' REMON NAIL & TAG W/S 12" OAK
EAST 13.56' REMON NAIL & TAG N/S 16" OAK



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

PEER GROUP ON 6-16-99, CO. REP JED

Signed by [Signature] Date NOV 9, 1999
Surveyor's Michigan License No. 29238