

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11:08

For corners in

LIVINGSTON  
(County)

Located in: BRIGHTON Corner Code #

9

HANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

- 1. Public Land Survey T 2N R 6E C-10  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
In Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

LSC# 1108m

Register of Deeds Stamp and File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Bryan L. Boss, in a field survey on OCTOBER 19, 1999  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

SET POST.  
OAK 13" S61W 38 LINKS  
OAK 16" N52E 46 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REROD AND CAP WITH CAP #23828 16' EAST OF EAST  
EDGE CONCRETE SHOULDER TO I-96, 800' MORE OR LESS SOUTH  
OF FLINT ROAD OVERPASS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1 1/4"X36" PIPE WITH BRASS CAP STAMPED  
"LIVINGSTON COUNTY REMONUMENTATION  
CORNER"  
S84°E 73.48' REMON NAIL & TAG N/S 8" ELM  
N18°E 24.82' REMON NAIL & TAG W/S 12" OAK  
S36°E 71.15' REMON NAIL & TAG NE/S 24" OAK  
N51°E 29.05' REMON NAIL & TAG NW/S 12" OAK



P.A. 305 1980, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 7-21-99, CO. REP. JED

Signed by [Signature]  
Surveyor's Michigan License No. 29238

Date Nov. 11, 1999