

OCT 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>2N</u> R <u>6E</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

HANCOY HAVILLAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843
OCT 4 3 18 PM '95

FILED

L.S.C. #443 m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Bryan Boss, in a field survey on 8-23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- Set half mile post
- Black Oak 14" N 42 E 1.39 chains
- Black Oak 8" N 85 W 25 links
- Black Oak 10" N 39 1/2 W 65 1/2 links
- Black Oak 10" S 81 E 42
-
- Black Oak 5" N 35 3/4 E 45.75
- Apple 16" S 51 1/2 W 55.75
- Black Oak 20" N.W. 56'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3/4" iron pipe found in monumnet box
centerline Van Amberg Road and Spencor Road
N 25° E 63.25 12" Maple
Re-established Livingston County Road Commission
field notes 1985 Walton Newton R.L.S. #30094

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set brass cap on 3/4" pipe in monument box
- 157.02' N 10° E nail & tag West side 36" Oak
- 63.22' N 45° E nail & tag West side 12" Maple
- 45.05' S 45° E stop sign post
- 121.68' S 50° W nail & tag North side 12" Elm
- 46.84' N 45° W nail & tag West side light pole



Signed by Bryan L. Boss Date SEP 29, 1995
Surveyor's Michigan License No. 29238

SUMMARY

G-10

West Corner, Section 27, T2N-R6E, Brighton Township,
Livingston County, Michigan.

Found 1/4" I.D. Iron pipe in monument box at centerline-
centerline of Van Amberg Road and Spencer Road.


We find that from 1972 field notes of Charles Garlock (pages
16-17) and all subsequent surveys through 1989 refer to 1/4"
pipe in monument box as the West 1/4 Corner of Section 27.

All existing surveyed distances are within acceptable
tolerances and it appears no other point has been used for
"G-10".

This road intersection is open for GPS.

Conclusion: We recommend acceptance of iron pipe in
monument box as found.

BRIG-10S



Bryan L. Boss