

FILED

Dec 28 4 17 PM '93

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston Located In: Corner Code ##
(County)

1. Public Land Survey	T	<u>2N</u>	R	<u>6E</u>	<u>K-9</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling In Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

L.S.C. #144m
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Bryan Boss, in a field survey on December 20, 1993,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Poplar 10" S62°E 29 Lks
W. Oak 10" N48°W 12 Lks
Restored by Grant Dunning County Surveyor in 1926

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found P. K. Nail

SURVEY &
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" x 30" Iron Rod and Raised with
1 1/4" x 36" I. Pipe with Brass Cap Marked
Livingston Co. Monument Corner in a Monument Box

S21°E 84.00' Spike E/Side Tele Pole
S82°W 121.00' Spike N/Side 18" Oak
N11°W 133.55' Spike E/Side Tele Pole
S31°W 73.65' Spike W/Side Tele Pole

Approved by Livingston Co.
Monumentation Peer Group
on October 13, 1993

Signed by Bryan Boss Date December 28, 1993
Surveyor's Michigan License No. 29238

