

FILED

Dec 29 11 26 AM '93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

For corners in

Livingston (County) Located In: Corner Code #

1. Public Land Survey T 1N R 5E K-12
 T R
 T R
 T R

2. Property Controlling S T R Sequence #1
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

L.S.C. #181m
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Bryan Boss, in a field survey on December 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Hickory 11 in. Dia. N94W 19 Lks.
 Hickory 8 in. Dia. S80E 35 Lks.

2N/6E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rerod at Intersection of Fences.

SURVEY &
 REMONUMENTATION
 1993
 COMMISSION


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1 1/4" x 36" Iron Pipe with Brass Cap
 (Livingston Co. Monument Corner)

West 2.95' Spike N/Side 10" Oak
 N83°E 29.93' Spike S/Side 30" Oak
 S30°E 15.60' Spike E/Side 24" Oak
 S30°W 60.23' Spike Power Pole
 S40°W 9.51' Spike Twin 9" Oak

Approved by Livingston Co.
 Monumentation Peer Group
 on September 8, 1993

Signed by [Signature]
 Surveyor's Michigan License No. 29238



Date December 28, 1993