

SURVEY & RECONSTRUCTION

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey
T 3N R 3E G3
T R _____
T R _____
T R _____
- 2. Property Controlling
in Section S T R _____
S T R _____
- 3. Miscellaneous
Property in Sec. S T R _____
S T R _____

1999 MAY 21 A 9:20

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#991m
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on APRIL 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.
GLO WITNESSES B ASH 10 S15W 7.26'
 B ASH 15 N27E 16.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" I. PIPE IN GRAVEL ROAD, ABOUT 3' WEST OF ROAD C/L AND INLINE WITH OLD FENCE LINE TO THE WEST.
WEST-33.00'-1/2" I. ROD CAP #14762

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G3: NW COR. SEC. 10 T3N-R3E HANDY TWP. LIV. CO. MI., REPLACED 1/2" I. ROD WITH 1 1/4" X 36" BREAKAWAY I. PIPE WITH LIV. CO. REMON CAP #14762
N60E-151.10'-SP & TAG N/S 10" ELM
S25E-124.12'-SP & TAG W/S U POLE
S30W-100.01'-SP & TAG E/S DBL 8" PIGNUT HICKORY
WEST-33.00'-1/2" I. ROD.



Signed by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date MAY 1, 1999

PA. 345 1999, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3-17-99, CO. REP JED