

MAR 17 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 MAY 21 A 9:21

For corners in SECTION

LIVINGSTON
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|----------|-----|
| 1. Public Land Survey | T3N R 3E | G 6 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling
in Section | S T R | |
| | S T R | |
| 3. Miscellaneous
Property in Sec. | S T R | |
| | S T R | |

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #994 m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on APRIL 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.
GLO WITNESSES ELM 7-S34E-1.98'
ELM 12-S85½W-12.54'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" I. PIPE ON TOP OF A LARGE POINTED STONE. 1' WEST OF ROAD C/L, INLINE WITH FENCE TO WEST AND DITCH TO THE EAST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G 6: W 1/4 COR. SEC. 15, T3N-R3E, HANDY TWP. LIV. CO. MI, RESET FOUND IRON WITH 1 1/4" X 36" BREAKAWAY I. PIPE WITH LIV. CO. REMON. CAP #14762
N35W-31.80'-SP & TAG E/S 7" POPLAR
N66E-46.32'-SP & TAG N/S 12" OAK
S50E-43.60'-SP & TAG S/S DBL 12" ASH
S36W-43.45'-SP & TAG E/S 6" ELM
EAST-33.00'-1/2" I. ROD #10699

Signed by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date MAY 1, 1999

