

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 MAY 21 A 9:21

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 3N R 3E G 7
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #995 III

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on APRIL 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.
GLO WITNESSES: W06 N44½W 1.98'
SUGUR 8 S32W 25.74'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: AND
FOUND RR SPIKE AT SURFACE OF ASPHALT ROAD THAT WAS ABOVE A FOUND BOAT SPIKE, /THE BOAT SPIKE
WAS ABOVE A FOUND 1" I. PIPE.
ALL IN THE C/L CROSSING OF THE ROAD INTERSECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G7: SW COR. SEC. 15, T3N-R3E, HANDY TWP. LIV. CO. MI, REPLACED FOUND IRONS WITH A 1¼" X 36"
BREAKAWAY I. PIPE WITH A LIV. CO. REMON CAP ON TOP, #14762 AND IN A SET MON. BOX.
S10E-74.60'-SP & TAG E/S MULTI 7" ELMS.
N40E-47.74'-SP 7 TAG W/S U POLE
S50W-134.90'-NE CORNER OF STONE HOUSE
S80W-153.70'-SP & TAG N/S 40" OAK

Signed by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date MAY 1, 1999

