

MAR 17 2000

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

LIVINGSTON
(County)

Located In:	Corner Code #
T <u>3N</u> R <u>3E</u>	<u>H3</u>
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

1999 MAY 21 A 9:21

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #996 m

Register of Deeds Stamp & File Number

1. Public Land Survey

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3							●					
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CHARLES E GARLOCK, in a field survey on APRIL 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO SURVEY DATED: APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.
GLO WITNESSES: B ASH 7-N3W-2.64'
TAM 10-S481/2E-1.98'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1 1/4" I. PIPE ABOUT 1.5' ABOVE GROUND WITH ALUM. CAP STAMPED H3 AND DATED 10/06/95
CORNER SET ON LINE WITH EAST AND WEST SECTION CORNERS AT 1/2 DISTANCE.
3 1/4" CAP STAMPED #19834 D HUGHES

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H3: N 1/4 COR. SEC. 10 T3N-R3E, HANDY TWP. LIV. CO. MI. AND LEFT THE FOUND I. PIPE IN PLACE.
SOUTH-45.00'-SP & TAG 6" ELM
S87W-213.57'-SP 7 TAG 6" TREE
N30W-302.02'-SP & TAG 12" ELM
S81E-190.72'-SP & TAG 18" WILLOW CUSTER
S45W-21.95'-C/L "T" POST IN E-W FENCE LINE.
SOUTH-1'-CARSONITE POST.



Signed by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date APRIL 5, 1999

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 3-17-99 CO. REP JED