

**SURVEY &  
REMONUMENTATION**

MAR 17 2000

**FILED**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

|                                       |  |               |
|---------------------------------------|--|---------------|
| <u>LIVINGSTON</u><br>(County)         | Located In:                            | Corner Code # |
| 1. Public Land Survey                 | T <u>3N</u> R <u>3E</u>                | <u>H 7</u>    |
|                                       | T <u>   </u> R <u>   </u>              | <u>   </u>    |
|                                       | T <u>   </u> R <u>   </u>              | <u>   </u>    |
|                                       | T <u>   </u> R <u>   </u>              | <u>   </u>    |
| 2. Property Controlling<br>in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>    |
|                                       | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>    |
| 3. Miscellaneous<br>Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>    |
|                                       | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>    |

1999 MAY 21 A 9:21

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C#998m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, CHARLES E GARLOCK, in a field survey on APRIL 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:  
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.  
GLO WITNESSES ELM 8-S2W-71.28'  
B ASH 8-S84½W-89.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND ½" I. ROD 1 FT. NORTH OF NORTH EDGE OF ASPHALT AND ON LINE WITH SE AND SW SECTION CORNERS AT ½ DISTANCE BETWEEN SAID SECTION CORNERS. RESET ½" I ROD WITH 1¼" X 36" BREAKAWAY I. PIPE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
H 7: S¼ COR. SECTION 15, T3N-R3E HANDY TWP. LIV. CO. MI. RESET WITH 1¼" X 36" BREAKAWAY  
I. PIPE WITH LIV. CO. REMON CAP ON TOP #14762  
N80E-92.69'-SP & TAG S/S 14" WILLOW  
N80W-89.10'-SP & TAG S/S 16" WILLOW  
NORTH-32.96'-1" X 36" I. PIPE W/LIV. CO. WITNESS CAP #14762;  
SOUTH-59.98'-1" X 36" I. PIPE W/LIV. CO. WITNESS CAP #14762  
SOUTH-11'-C/L OF ASPHALT ROAD.

Signed by Charles E. Garlock  
Surveyor's Michigan License No. 14762

Date MAY 1, 1999

