SURVEY & REMONUMENTATION

FEB 2 5 1999

SECTION LAND CORNER RECORDATION CERT	
For corners in	
LIVINGSTON Located In: Corner Code #	9 1998 AUG 20 P 4: 44
1. Public Land Survey T3N R3E 17 T R	NANCY HAVILAND REGISTER OF DEEDS LIVINGSTON COUNTY, MI. 48843
2. Property Controlling S T R	L.S.C. #871m
Property in Sec. S TR	Register of Deeds Stamp & File Number
4. Lot No, Recorded Plat	
5. Private Claims	1 B C D E F G H I J K L I
I, CHARLES E. GARLOCK, in a field survey on AUG. 7, 19 98 do hereby state that a requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above we conformance with regulations and rules therefore as required in the current manual of survey instructions. United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law at that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Mic Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monume recovered, found as expressed below:	ere in of the 5
NOTE: Not more than 2 corners, all in the same town and range, may be recorded	9
on this certificate.	10 30 29 28 27 26 25
	12 31 32 33 34 35 36
A. Description of original monument and accessories and/or subsequent restoration: GLO SURVEY DATED: APRIL 15, 1825 BY S. SIBLEY, DS GLO WITNESSES: MAPLE 13-S53E-10 LKS MAPLE 12-N59W-17 LKS	CHARLES E. GARLOCK PROPESSIONAL SURVEYOR NO. 14782
ADDITIONAL DATA ON REAR OF SHEET	OFESSION
B. Description of corner evidence found and/or method applied in restoring or reestablishing	ng corner:
FOUND A SQUARE HEADED BOLT IN A MON. BOX ON CENTERLINE OF LINE OF ROAD TO THE WEST AND OCCUPATION TO THE EAST.	FOWLERVILLE ROAD AND CENTER-
C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 17: NW COR. SEC. 23 T3N-R3E, HANDY TWP. LIV. CO. MI, REPLACED BOLT WITH 1½" X 36" BREAK-AWAY I. PIPE WITH LIV. REMON. BRASS CAP ON TOP. N85W-132.52'-SP & TAG S/S DBL 12" ELM N15E-138.18'-SP & TAG W/S 20" BOX ELDER N50E-31.61'-SP & TAG N/S 8" ELM N60E-99.82'-SP 7 TAG S/S 18' MAPLE ON CTR. OF FOWLERVILLE RD AND SOUTH 3' TO CTR OF VAN BUREN RD.	
Signed by Date	AUGUST 8, 1998
Surveyor's Michigan License No. 14762	