

SURVEY & REMONUMENTATION

FEB 25 1999

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>3E</u>	<u>I11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

91
1998 AUG 20 P 4:45
NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843
L.S.C. #875m
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on AUG 7, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED: APRIL 15, 1825 BY S SIBLEY, DS
GLO WITNESSES : SUGAR 8 STANDS FOR CORNER

ADDITIONAL DATA ON REAR OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" I. ROD AT CENTERLINE INTERSECTION OF ROADS
FOUND MORE IRON UNDER THE 1/2" I. ROD AT -2.5' FOUND A 3" DIA PIPE THAT WAS 0.1' NORTH AND 0.1' EAST OF THE 1/2" I. ROD, ALSO FOUND SEVERAL FLAT IRONS USED FOR IRONING YEARS AGO AND A PLOW POINT.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I11: SW COR. SEC. 26 T3N-R3E HANDY TWP. LIV. CO. MI, RESET 1/2" I. ROD WITH 1 1/2" X 36" BREAK-AWAY I. PIPE IN A MON BOX WITH A LIV. CO. REMON. BRASS CAP ON TOP.
THE 1 1/4" X 36" PIPE ACTUALLY WAS SET 0.1' NORTH AND 0.1' EAST OF THE 1/2" I. ROD INSIDE OF THE FOUND 3" DIA. PIPE.
N15W-131.70'-SP & TAG E/S 15" CEDAR
N45W-52.02'-SP & TAG S./S U POLE
S45W-46.08'-SP & TAG N/S U POLE
N30E-47.15'-SP & TAG W/S U POLE
EAST-1'-CTR. FOWLerville RD N-S
ON CTR. SARGENT ROD TO THE EAST
4' SOUTH TO CTR SARGENT RD TO WEST

Signed by Charles E. Garlock Date AUGUST 8, 1998
Surveyor's Michigan License No. 14762

PA. 348 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 2/18/98, CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985