

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

1999 MAY 21 A 9:21

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

Seg. 1

L.S.C.#1003m

Register of Deeds Stamp & File Number

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T3N R 3E	J 3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, CHARLES E GARLOCK, in a field survey on APRIL 28 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.
GLO WITNESSES W026-S66½W-28.38'
W014-N28½W-31.68'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" I. ROD ABOVE A FOUND PLOW POINT. PLOW POINT IN MC CREARY'S 1900 DESCRIPTION OF THIS CORNER. ALSO FOUND 1/2" I. ROD SET BY BOSS ENGR IN 1980, LOCATED 15.23' EASTERLY OF THE ABOVE FOUND IRON AND PLOW POINT. OLD OCCUPATION LINE NORTH AND SOUTH COMES CLOSER TO MATCHING THE MC CREARY PLOW POINT THAN THE BOSS ENGR IRON.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J3: N1/4 COR. SEC. 11, T3N-R3E, HANDY TWP. LIV. CO. MI. REPLACED FOUND IRON ROD AND PLOW POINT WITH 1½" X 36" BREAKAWAY I. PIPE W/LIV. CO. REMON CAP ON TOP #14762
S89W-153.95'-SP & TAG N/S 36" OAK
S60W-44.45'-SP & TAG N/S 24" OAK
S20W-40.86'-SP & TAG W/S DBL 30" MAPLE
S53E-80.10'-SP & TAG N/S DBL 36" MAPLE
SOUTH-3'-C/L SHARPE ROAD

Signed by *Charles E. Garlock*
Surveyor's Michigan License No. 14762

Date MAY 1, 1999

