

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 MAY 21 A 9:22

For corners in

LIVINGSTON
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 3N R 3E J5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#1004m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on APRIL 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED: APRIL 15, 1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.
GLO WITNESSES: TAM 6-N87½E-264'
 ASPIN 10-S78W-67.32'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT AT -0.5' ABOUT 4' NORTH OF C/L OF E-W GRAVEL ROAD.
ALSO LINES WITH FENCE LINE NORTH AND SOUTH

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J3: S¼ COR. SEC. 11 T3N-R3E HANDY TWP. LIV. CO. MI. SET SPECIAL LIV. CO. REMON. CAP ON TOP OF FOUND CONCRETE MONUMENT #14762
NORTH-22.38'-C/L 2" STEEL POST IN CONCRETE
N45W-13.80'-SP & TAG W/S U POLE
N45W-24.78'-C/L TOP NUT ON FIRE HYDRANT
SOUTH-29.78'-FACE OF 12" CONCRETE POST
S60E-63.55'-SP & TAG N/S 7" ASH

Signed by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date MAY 1, 1999

