

**SURVEY & REMONUMENTATION**

FEB 25 1999

**FILED**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

LIVINGSTON  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 3N R 3E J7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

9/

1998 AUG 20 P 4:44

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C. #869m  
Register of Deeds Stamp & File Number

I, CHARLES E GARLOCK, in a field survey on JULY 31, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY  
GLO WITNESSES: BEECH 12-S42W-9 LKS  
BEECH 10-N62½E-19 LKS



ADDITIONAL DATA ON REAR OF SHEET.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ½" I. ROD PREVIOUSLY SET ON LINE BETWEEN NE & NW SECTION CORNERS AT ½ DISTANCE, WHICH LINES WITH FENCE LINE TO NORTH AND WITHIN 1' OF EAST-WEST FENCE LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J7: N ¼ COR. SEC. 23 T3N-R3E HANDY TWP., LIV. CO. MI, RESET: FOUND ½" I. ROD WITH 1¼" X 36" I. PIPE WITH LIV., CO, REMON BRASS CAP ON TOP.  
N38W-30.39'-SP & TAG W/S 10" OAK  
N31E-10.49'-SP & TAG W/S 5" ELM  
N65W-48.20'-SP & TAG S/S 9" OAK  
N2W-48.21'-SP & TAG E/S 28" OAK

Signed by Charles E. Garlock  
Surveyor's Michigan License No. 14762

Date AUGUST 8, 1998