

**SURVEY & REMONUMENTATION**

FEB 25 1999

**FILED**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

1998 AUG 20 P 4: 44

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C. #868m

Register of Deeds Stamp & File Number

For corners in

LIVINGSTON  
(County)

Located In:

Corner Code #

1. Public Land Survey

T	3N	R	3E	J9
T		R		
T		R		
T		R		
S		T	R	
S		T	R	
S		T	R	
S		T	R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, CHARLES E GARLOCK, in a field survey on AUG. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY, DS  
GLO WITNESSES: ELM 12-N64½W-4 LKS  
BEECH 8-S64½E-16 LKS.



ADDITIONAL DATA ON REAR OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1½" PIPE ON CENTERLINE OF ROAD NORTH AND SOUTH AND IN LINE WITH FENCE LINE TO WEST, NO OCCUPATION TO THE EAST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
J9: S¼ COR. SEC. 23 T3N-R3E, HANDY TWP. LIV. CO. MI., . RESET 1½" PIPE WITH 1¼" X 36" BREAKAWAY I. PIPE WITH LIV. CO. REMON BRASS CAP ON TOP.  
S70E-22.35'-SP & TAG S/S 45" WALNUT  
S78W-28.19'-SP & TAG N/S 8" OAK  
WEST-24.61'-SP & TAG S/S 12" OAK  
N44W-144.20'-ONE CORNER OF HOUSE.

Signed by Charles E. Garlock  
Surveyor's Michigan License No. 14762

Date AUGUST 8, 1998

PA. 345 1880, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 3/18/98 CO. REP JED