

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston (County)

Located In:

Corner Code #

FILED

AUG 27 10 25 AM '96

NANCY HAVILANG REGISTER OF DEEDS LIVINGSTON COUNTY, MI. 48843

L.S.C.#546m

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3N R 3E K-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked in the top right corner of the grid.

Charles E Garlock in a field survey on July 22, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: GLO survey dated April 15, 1825 by S Sibley, DS GLO witnesses: W011-S29E-22 lks W012-S81W-58 lks

Additional historical data on rear of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 5/8" I. Rod 0.83 ft. North of East-West Township line.



PA. 345 1980, APPROVED BY LIVINGSTON COUNTY PEER GROUP ON 4-17-96 CO. REP JED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: K-1: NW cor. Sec. 1 T3N-R3E, Handy Twp. Liv. Co. MI. set 1 1/4" X 36" breakaway I. Pipe at 0.5' with Liv.Co. Remon brass cap on top on the East-West Township line and East line of Sec. 1 extended at 0.83 ft. South of the found corner. Set an Amended cap on the Found corner of Alum. constr. Witnesses to brass cap are: S16W-29.39'-sp & tag E/s 22" Cherry N67E-56.23'-sp & tag S/s 36" maple S42W-24.84'-sp & tag N/s 14" Maple S60W-32.59'-sp & tag N/s 8" dbl Hickory N60W-73.82'-sp & tag S/s 11" R Oak South-32.17'-1/2" I. Rod capped "Boss" corner is on c/l E-W Road North-0.83' Amended Corner 5/8" I.R.

Signed by [Signature] Date July 24, 1996 Surveyor's Michigan License No. 14762

CORNER SUMMARY

K-1: NORTHWEST CORNER SECTION 1, T3N-R3E, HANDY TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN.

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY, DS, AND NONE OF THE
GLO WITNESSES REMAIN.

M BULLOCK WITNESSED THIS CORNER IN 1875 AND NONE REMAIN; I TELLER
IN 1888 SAID HE FOUND THE REMAINS OF THE GLO CORNER AND SET A
STONE 36" X 12" X 10" IN ITS PLACE AT A POINT 67.98 FEET EAST OF
THE CONWAY CORNER WHICH IS THE GLO JOG OF 1.03 CHAINS AND WE
MEASURED 68.15 FEET. IN 1970 VERBA WITNESSED THIS CORNER AND THE
ONE THAT REMAINS CHECKS. BOSS WITNESSED IT IN 1976 AND 1994,
FIVE REMAIN AND CHECK. WE FOUND A 5/8" I. ROD IN LINE WITH A
HEDGE TO THE SOUTH, INLINE WITH THE CENTERLINE OF A ROAD THAT
ANGLES NORTHWESTERLY AND 1-2 FEET SOUTH OF THE ROAD RUNNING EAST
AND WEST. FOUND ONE ACT 74 AND FIVE ACT 132'S RECORDED. MEASURES
WEST OF 2625.91 BY BOSS, MEASURES EAST ARE: 2621.79 BY VERBA,
2622.20 BY MYSELF AND 2598.42 FROM OLD SURVEY RECORDS. MEASURE
SOUTH ARE: 2082.45 BY BOSS, 2082.99 BY VERBA, 2098.14 AND 2108.04
FROM OLD SURVEY RECORDS. WE DID NOT FIND TELLER'S STONE, BUT
FOUND THE CONWAY CORNER WITHIN 0.17 FEET OF GLO JOG AND BOTH
CORNERS LINE WITH OCCUPATION IN THEIR RESPECTIVE TOWNSHIPS. THE
NORTHWEST CORNER OF SECTION 1 IS LOCATED 0.83 FEET NORTH OF THE
TOWNSHIP LINE. RECOMMEND WE ACCEPT THE FOUND CORNER IN THE GRAVEL
ROADWAY, TOO MANY OVERHANGING TREES FOR A GPS SITE.



CHARLES E GARLOCK
PS 14762

HAN96K1

T3N R3E K1 4