

SURVEY & REMONUMENTATION

OCT 25 1993

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Livingston
COMMISSION
(County)

Located In: _____ Corner Code ##

- | | | | | | |
|---------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey | T | <u>3N</u> | R | <u>3E</u> | <u>K-11</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling
in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

FILED
 AUG 26 9 12 AM '93
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

2m
L.S.C# _____
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles E garlock, in a field survey on August 24, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO notes: Beech 11-N641/2E-151ks
R Oak 30-N78W-36 lks
 A 1981 witness to an 18" Maple matches the 1882 witness to a 3" Maple by M W Bullock, County Surveyor and witness OK in 1993, N45E-31.65' (0.48 lks)-18" maple

GLO notes April 15, 1825, S. Sibley

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" X 15" lead pipe in centerline of Sargent and Smith Roads.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 1 1/4" X 30" I. Pipe raised with 1 1/4" X 6" I. Pipe with brass cap marker: Liv. Co.
 Mon. Cor. at (-0.5')
 N15W-92.67'-spike E/side 15" Maple
 N75W-136.92'-spike N/side U. Pole
 N45E-31.34'-spike W/side 18" Maple
 S80E-164.80'-spike N/side 36" W Oak
 on the centerline of road intersections of Smith and Sargent Roads

APPROVED; by Livingston County Monumentation Peer Group, July 21, 1993

Signed by *Charles E Garlock* Date August 25, 1993
 Surveyor's Michigan License No. 14762

10/26/93